

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT AN APPLICATION

Other instructions on reverse side)

MAR 4 1996

Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

LEASE DESIGNATION AND SERIAL NO.

U-36442

IF INDIAN, ALLOTTEE OR TRIBE NAME

UNIT AGREEMENT NAME

FARM OR LEASE NAME

Federal

WELL NO.

13-28

FIELD AND POOL, OR WILDCAT

Eight Mile Flat North

SEC., T., R., M., OR BLK.
AND SURVEY OR AREA

Section 28, T8S, R18E

COUNTY OR PARISH

Uintah

STATE

Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK
OF OIL, GAS & MINING

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒

GAS
WELL ☐

OTHER

SINGLE
ZONE ☒

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Wildrose Resources Corporation

PH: 303-770-6566

3. ADDRESS OF OPERATOR

4949 South Albion Street, Littleton, CO 80121

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface

704' FWL & 2007' FSL (NW $\frac{1}{4}$ SW $\frac{1}{4}$)

At proposed prod. zone

Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

11 miles SE of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. unit line, if any)

687'

16. NO. OF ACRES IN LEASE

1447.3

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

4000'

19. PROPOSED DEPTH

6200'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4955' GR

22. APPROX. DATE WORK WILL START*

April 15, 1996

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#, J-55	300'	225 SX
7-7/8"	5-1/2"	15.5#, J-55	6200'	800 SX

SEE ATTACHED EXHIBITS: A - Surveyors Plat E - Access Road Map
B - 10 Point Plan F - Production Facilities
C - BOP Diagram G - Existing Wells Map
D - 13 Point Surface Use Program H - Pit & Pad Layout, Cuts & Fills,
Cross Sections, Rig Layout

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Ray J. Kattenbach

TITLE

Vice President

DATE

March 1, 1996

(This space for Federal or State office use)

PERMIT NO.

43-047-32743

APPROVAL DATE

APPROVED BY

R. Matthews

TITLE

Petroleum Engineer

DATE



4/8/96

CONDITIONS OF APPROVAL, IF ANY

*See Instructions On Reverse Side

WILDROSE RESOURCES CORP.
WELL LOCATION PLAT
FEDERAL #13-28

LOCATED IN THE NW1/4 OF THE SW1/4 OF
 SECTION 28, T8S, R18E, S.L.B.&M.




SCALE: 1" = 1000'

LEGEND AND NOTES

- ◇ ORIGINAL MONUMENTS FOUND AND USED BY THIS SURVEY.

THE GENERAL LAND OFFICE (G.L.O.) PLAT WAS USED FOR REFERENCE AND CALCULATIONS AS WAS THE U.S.G.S. QUADRANGLE MAP.




SURVEYOR'S CERTIFICATE

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY PERFORMED BY ME, DURING WHICH THE SHOWN MONUMENTS WERE FOUND OR ESTABLISHED.

Jerry D. Allred
 JERRY D. ALLRED, REGISTERED LAND SURVEYOR,
 CERTIFICATE NO. 148951 (UTAH)

Exhibit 'A'



JERRY D. ALLRED & ASSOCIATES
 SURVEYING CONSULTANTS

121 NORTH CENTER STREET
 P.O. BOX 975
 DUCHESNE, UTAH 84021
 (801)-738-5352

16 FEB 1996

83-123-023

EXHIBIT B

WILDROSE RESOURCES CORPORATION
FEDERAL #13-28
LEASE #U-36442
NW/SW SECTION 28, T8S, R18E
UINTAH COUNTY, UTAH

TEN POINT COMPLIANCE PROGRAM OF APPROVAL OF OPERATIONS

1. The Geologic Surface Formation

The surface formation is the Uintah (Tertiary).

2. Estimated Tops of Important Geologic Markers

Green River	1700'
Wasatch Tongue of Green River	6100'
Total Depth	6200'

3. Estimated Depths of Anticipated Water, Oil, Gas or Minerals

No water bearing zones are anticipated

Green River 4000' - 6200' Oil

4. The Proposed Casing Program

<u>HOLE</u>	<u>INTERVAL</u>	<u>LENGTH</u>	<u>SIZE(OP)</u>	<u>WEIGHT, GRADE, JOINT</u>	<u>NEW OR USED</u>
12.25"	0 - 300'	300'	8-5/8"	24# K-55 ST&C	New
7-7/8"	0 - 6200'	6200'	5-1/2"	15.50# J-55 ST&C	New

Cement Program -

Surface Casing: 225 sacks Class "G" plus 2% CaCl₂

Production Casing: 200 sacks Lite Cement and 600 sacks Class "G" with additives

5. The Operator's Minimum Specifications for Pressure Control

EXHIBIT "C" is a schematic diagram of the blowout preventer equipment. A 2M system will be used. The blind rams and the pipe

rams will be tested to 1500 psi after nipping up and after any use under pressure. Pipe rams will be operationally checked each 24 hour period, as will blind rams and annular preventer each time pipe is pulled out of the hole. Such checks of BOP will be noted on daily drilling reports.

Accessories to BOP will include an upper kelly cock, floor safety valve, drill string BOP and choke manifold with pressure rating equivalent to the BOP stack.

6. The Type and Characteristics of the Proposed Circulating Muds

Mud system will be 2% KCl water with adequate stocks of sorptive agents on site to handle possible spills of fuel and oil on the surface. Heavier muds will be available to be added if pressure requires.

<u>DEPTH</u>	<u>TYPE</u>	<u>WEIGHT #/gal</u>	<u>VISCOSITY sec/qt</u>	<u>FLUID LOSS cc</u>	<u>PH</u>
0-4000'	Fresh Water	8.4 - 8.6	28 - 30	NC	--
4000-6200'	2% KCl Water	8.6 - 8.8	30 - 34	NC	9.0

7. The Auxiliary Equipment to be Used

- a) An upper kelly cock will be kept in the string.
- b) A float will be used at the bit.
- c) A mud logging unit will not be used. Mud system will be visually monitored.
- d) A stabbing valve will be on the floor to be stabbed into the drill pipe when kelly is not in the string.

8. The Testing, Logging and Coring Programs to be Followed

- a) No Drill Stem Tests will be run.
- b) The Logging Program: Dual Later Log 300' - T.D.
Formation Density-CNL 4000' - T.D.
- c) No coring is anticipated.
- d) Stimulation procedures will be determined after evaluation of logs. If treatment is indicated, appropriate Sundry Notice will be submitted for approval.

9. Any Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures have been noted or reported in wells drilled in the area nor at the depths anticipated in this well. Bottom hole pressure expected is 1500 psi + or -.

No hydrogen sulfide or other hazardous fluids or gases have been found, reported or known to exist at these depths in the area.


10. Anticipated Starting Date and Duration of the Operations.

The anticipated starting date is April 15, 1996. Operations will cover approximately 10 days for drilling and 14 days for completion.

Hazardous Chemicals

No chemicals subject to reporting under SARA title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling of this well.

EXHIBIT C
BOP DIAGRAM



NOTE: BOP side outlets may be used in place of drilling spool.




EXHIBIT D

WILDROSE RESOURCES CORPORATION
FEDERAL #13-28
LEASE #U-36442
NW/SW SECTION 28, T8S, R18E UINTAH COUNTY, UTAH

Thirteen Point Surface Use Program

Multipoint Requirements to Accompany APD

1. Existing Roads

- A. The proposed well site and elevation plat is shown on Exhibit A.
- B. From Fort Duchesne go south 6 miles to bridge. Go across bridge and follow Leland Bench road 13.2 miles. Go right 0.2 miles. Go right 0.8 miles. Go left (west) 5.0 miles to location on the left.
- C. See Exhibit E for access roads.
- D. There are no plans for improvement of existing roads. Roads will be maintained in present condition.

2. Planned Access Roads - (Newly Constructed)

- A. Length - 1000 feet.
- B. Width - 30' right of way with 18' running surface maximum.
- C. Maximum grades - 5%
- D. Turnouts - N/A
- E. Drainage design - Barrow ditches and water turnouts as required.
- F. Culverts, bridges, cuts and fills - None.
- G. Surfacing material (source) - from location and access road.
- H. Gates, cattle guards and fence cuts - None.

All travel will be confined to existing access road rights of way.
Access roads and surface disturbing activities will conform to

standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).

The road shall be upgraded to meet the standards of the anticipated traffic flow and all weather road requirements. Construction/ upgrading shall include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot right of way will not be allowed. Road drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diversion water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

A Right of Way application is needed and will be prepared by the BLM.

3. Location of Existing Wells Within a 1 Mile Radius

See Exhibit G

- A. Water wells - none.
- B. Abandoned wells - three.
- C. Temporarily abandoned wells - none.
- D. Disposal wells - none.
- E. Drilling wells - none.
- F. Producing wells - five.
- G. Shut-in wells - none.
- H. Injection wells - none.

4. Location of Existing and/or Proposed Facilities

- A. On well pad - See Exhibit F for all production facilities to be used if well is completed as a producing oil well.
- B. Off well pad - N/A

If a tank battery is constructed on this lease, the battery or the well pad will be surrounded by a dike of sufficient capacity to

contain, at a minimum, the entire content of the largest tank within the battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

Tank battery will be placed on the SE corner of the location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rock Mountain Five state Interagency Committee. All facilities will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is desert brown, 10YR.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligation as determined by the authorized officer.

5. Location and Type of Water Supply

- A. Water supply will be from Water Permit #43-1721 (Joe Shields spring).
- B. Water will be trucked across existing roads to location.
- C. No water wells to be drilled on lease.

6. Source of Construction Materials

- A. Native materials on lease will be used.
 - B. From Federal land.
 - C. N/A.
- A minerals material application is not required.

7. Methods for Handling Waste Disposal

- A.
 - 1) Drill cuttings will be buried in the reserve pit.
 - 2) Portable toilets will be provided for sewage.

3) Trash and other waste material will be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

4) Salts - if any will be disposed of.

5) Chemicals - if any will be disposed of.

B. Drilling fluids will be handled in the reserve pit. Any fluids produced during testing operations will be collected in a test tank. If a test tank is not available during drilling, fluids will be handled in the reserve pit. Any oil in the reserve pit will be removed.

Burning will not be allowed. All trash must be contained in trash cage and hauled away to an approved disposal site at the completion of drilling activities.

The reserve pit shall be constructed so as not to leak, break, or allow discharge.

A plastic nylon reinforced liner will be used. It will be a minimum of 12 mil thickness with sufficient bedding (either straw or dirt) to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. More stringent protective requirements may be deemed necessary by the A.O.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days. During the 90 day period, in accordance with Onshore Order No. 7, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. Ancillary Facilities

A. Camp facilities or airstrips will not be required.

9. Well Site Layout

A. See Exhibit H.

B. See Exhibit H.

C. See Exhibit H.

The reserve pit will be located on the east side of the location.

The flare pit will be located downwind of the prevailing wind direction on the east side of the location a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

Topsoil - will be stored along the west side of the location.

Access to the well pad will be from the south.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

a. 39-inch net wire shall be used with at least one strand of barbed wire on top of the net wire (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).

b. The net wire shall be no more than 2-inches above the ground. The barbed wire shall be 3-inches above the net wire. Total height of the fence shall be at least 42-inches.

c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

d. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16 feet.

e. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

10. Plans for Restoration of Surfaces

A. Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all debris, materials, trash and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with 43 CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 120 days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed and all cans, barrels, pipe, etc., will be removed.

The BLM will be contacted for required seed mixture.

B. Dry Hole/ Abandoned Location:

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. Surface Ownership

Access Road: Federal
Location: Federal

12. Other Additional Information

A. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to:

- Whether the materials appear eligible for the National Register of Historic Places;

- The mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and

- A time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from

the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

B. The operator will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list of noxious weeds may be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land it is required that a Pesticide Use Proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

C. Drilling rigs and/or equipment used during drilling operations on this wellsite will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

Additional Surface Stipulations

The well pad will be rounded off at the southeast corner (point 6) of the location.

Reclamation of unused disturbed areas on the well pad/access road no longer needed for operations, such as cut slopes, and fill areas will be accomplished by grading, leveling and seeding as recommended by the Authorized Officer.

13. Lessee's or Operators Representative and Certification Representative

Kary J. Kaltenbacher
Wildrose Resources Corporation
4949 South Albion Street
Littleton, CO 80121
Telephone: 303-770-6566

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved plan of operations, and any applicable Notice to Lessees. The operator is fully responsible for the actions of his sub-contractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A complete copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities.

The operator or his/her contractor shall contact the BLM Office at (801) 789-1362 forty eight (48) hours prior to

construction activities.

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.


Self-Certification Statement:

Please be advised that Wildrose Resources Corporation is considered to be the operator of Federal Well No. 13-28, NW/4 SW/4 of Section 28, Township 8 South, Range 18 East; Lease Number U-36442; Uintah County, Utah; and is responsible for the operations conducted upon the leased lands. Bond coverage is provided by Statewide Oil and Gas Bond No. 229352, Allied Mutual Insurance Company, approved by the BLM effective October 26, 1987.

Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and, that the work associated with the operations proposed here will be performed by Wildrose Resources Corporation and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date 3/1/96


Kary J. Kaltenbacher
Vice President

Onsite Date: February 28, 1996


Participants on Joint Inspection

Everett R. Wilcken
Byron Tolman
Jean Sinclair
Steve Strong

Wildrose Resources Corporation
BLM
BLM
BLM

CONFIDENTIAL STATEMENT

WILDROSE RESOURCES CORPORATION, AS OPERATOR, REQUESTS THAT ALL INFORMATION RELATED TO THIS WELL BE HELD TIGHT FOR THE MAXIMUM PERIOD ALLOWED BY FEDERAL AND STATE REGULATIONS.



TOPOGRAPHIC
MAP "A"



WILDROSE RESOURCES CORP.

FEDERAL #13-28
SECTION 28, T8S, R18E, S.L.B.&M.


Exhibit 'E'

23 Feb '96


83-123-023

Access Road


EXHIBIT F
PRODUCTION FACILITIES
SCALE: 1" = 40'






North



WILDROSE RESOURCES CORP.
WELL LAYOUT PLAT
FEDERAL #13-28



LOCATED IN THE NW1/4 OF THE SW1/4 OF SECTION 28,
 TOWNSHIP 8 SOUTH, RANGE 18 EAST, S.L.B.&M.



APPROXIMATE QUANTITIES

CUT: 5200 CU. YDS. (INCLUDES PIT)
 FILL: 2800 CU. YDS.

21 FEB 1996

83-123-023

Exhibit 'H'

JERRY D. ALLRED & ASSOCIATES
 SURVEYING AND ENGINEERING CONSULTANTS
 121 NORTH CENTER STREET
 P.O. BOX 975
 DUCHESNE, UTAH 84021
 (801) 738-5352

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/04/96

API NO. ASSIGNED: 43-047-32743

WELL NAME: FEDERAL 13-28
OPERATOR: WILDROSE RESOURCES CORP (N9660)

PROPOSED LOCATION:
NWSW 28 - T08S - R18E
SURFACE: 0704-FWL-2007-FSL
BOTTOM: 0704-FWL-2007-FSL
UINTAH COUNTY
EIGHT MILE FLAT NORTH FIELD (095)

LEASE TYPE: FED
LEASE NUMBER: U-36442

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Federal ☒ State ☐ Fee ☐
(Number 229352)
☒ Potash (Y/N)
☒ Oil shale (Y/N)
☒ Water permit
(Number 43-1721)
☒ RDCC Review (Y/N)
(Date: _____)

LOCATION AND SITING:

☐ R649-2-3. Unit: _____
☒ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: _____

STIPULATIONS: _____

STATE OF UTAH, DIV OF OIL, GAS & MINERALS

Operator: WILDROSE RESOURCES COR	Well Name: FEDERAL 13-28
Project ID: 43-047-32743	Location: SEC. 28 - T08S - R18E

Design Parameters:

Mud weight (8.80 ppg) : 0.457 psi/ft
 Shut in surface pressure : 2568 psi
 Internal gradient (burst) : 0.043 psi/ft
 Annular gradient (burst) : 0.000 psi/ft
 Tensile load is determined using air weight
 Service rating is "Sweet"

Design Factors:

Collapse : 1.125
 Burst : 1.00
 8 Round : 1.80 (J)
 Buttress : 1.60 (J)
 Other : 1.50 (J)
 Body Yield : 1.50 (B)

Length (feet)	Size (in.)	Weight (lb/ft)	Grade	Joint	Depth (feet)	Drift (in.)	Cost
1	6,200	5.500	15.50	J-55	ST&C	6,200	4.825

	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	S.F.
1	2834	4040	1.426	2834	4810	1.70	96.10	202	2.10 J

Prepared by : MATTHEWS, Salt Lake City, Utah
 Date : 04-08-1996
 Remarks :

Minimum segment length for the 6,200 foot well is 1,500 feet.
 SICP is based on the ideal gas law, a gas gravity of 0.75, and a mean gas
 temperature of 119°F (Surface 74°F , BHT 161°F & temp. gradient 1.400°/100 ft.)
 String type: Production
 The mud gradient and bottom hole pressures (for burst) are 0.457 psi/ft and
 2,834 psi, respectively.

NOTE: The design factors used in this casing string design are as shown above. As a general
 guideline, Lone Star Steel recommends using minimum design factors of 1.125 - collapse (with
 evacuated casing), 1.0 - (uniaxial) burst, 1.8 - API 8rd tension, 1.6 - buttress tension,
 1.5 - body yield tension, and 1.6 - EUE 8rd tension. Collapse strength under axial tension
 was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility
 for use of this design will be that of the purchaser.
 Costs for this design are based on a 1987 pricing model. (Version 1.07)



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

April 8, 1996

Wildrose Resources Corporation
4949 S Albion St
Littleton, Colorado 80121

Re: Federal #13-28 Well, 2007' FSL, 704' FWL, NW SW, Sec. 28,
T. 8 S., R. 18 E., Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-32743.

Sincerely,

A handwritten signature in black ink, appearing to read 'R. J. Firth'.

R. J. Firth
Associate Director

lwp

Enclosures

cc: Uintah County Assessor

Bureau of Land Management, Vernal District Office

WAPD



Operator: Wildrose Resources Corporation
Well Name & Number: Federal #13-28
API Number: 43-047-32743
Lease: U-36442
Location: NW SW Sec. 28 T. 8 S. R. 18 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN OR PLUG BACK

1A. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

B. TYPE OF WELL

OIL
WELL ☒

GAS
WELL ☐

OTHER

SINGLE
ZONE ☒

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Wildrose Resources Corporation

PH: 303-770-6566

3. ADDRESS OF OPERATOR

4949 South Albion Street, Littleton, CO 80121

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface

704' FWL & 2007' FSL (NW $\frac{1}{4}$ SW $\frac{1}{4}$)

At proposed prod. zone

Same

43-047-32743

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

11 miles SE of Myton, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drlg. unit line, if any)

687'

18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

4000'

16. NO. OF ACRES IN LEASE

1447.3

19. PROPOSED DEPTH

6200'

17. NO. OF ACRES ASSIGNED
TO THIS WELL

40

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4955' GR

22. APPROX. DATE WORK WILL START*

April 15, 1996

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8"	24#, J-55	300'	225 sx
7-7/8"	5-1/2"	15.5#, J-55	6200'	800 sx

SEE ATTACHED EXHIBITS:

A - Surveyors Plat

B - 10 Point Plan

C - BOP Diagram

D - 13 Point Surface Use Program

E - Access Road Map

F - Production Facilities

G - Existing Wells Map

H - Pit & Pad Layout, Cuts & Fills,
Cross Sections, Rig Layout

CONDITIONS OF APPROVAL ATTACHED

RECEIVED

MAR 04 1996

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Ray J. Kattenbach

TITLE

Vice President

DATE

March 1, 1996

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

ASSISTANT DISTRICT

APR 08 1996

APPROVED BY

TITLE

MANAGER MINERALS

DATE

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

*See Instructions On Reverse Side

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Wildrose Resources Corporation

Well Name & Number: Federal 13-28

API Number: 43-047-32743

Lease Number: U-36442

Location: NWSW Sec. 28 T. 8S R. 18E

NOTIFICATION REQUIREMENTS

- | | | |
|---------------------------------|---|---|
| Location Construction | - | at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - | prior to moving on the drilling rig. |
| Spud Notice | - | at least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing | - | at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - | at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - | within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report **ALL** water shows and water-bearing sands to Tim Ingwell of this office **prior to setting the next casing string or requesting plugging orders**. Faxed copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 2M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

If conductor pipe is set it shall be cemented to surface. If drive pipe is used it shall be pulled prior to cementing surface casing.

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the Usable Water zone identified at ± 290 ft., or by extending the surface casing to ± 340 ft. and having a cement top at least 200' above the Mahogany Oil Shale, identified at ± 3290 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to ± 3090 ft. if the surface casing is set at ± 340 ft. or to the **surface** if the surface casing is set at ± 300 ft.. The CBL shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours prior to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.), and shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approval or notification is necessary, please contact one of the following individuals:

Wayne P. Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

Jerry Kenczka (801) 789-1190
Petroleum Engineer

BLM Fax Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE USE PROGRAM

The topsoil should be piled around the north end of the location to create a noise buffer between the well and the cliffs to the north. This would mitigate the noise levels to potential raptor habitate to the north.

A representative from the BLM should be present during the initial construction of the road and well pad to monitor for paleontological disturbance.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: WILDROSE

Well Name: FEDERAL 13-28

Api No. 43-047-32743

Section 28 Township 8S Range 18E County UINTAH

Drilling Contractor UNION

Rig #: 16

SPUDDDED:

Date: 5/2/96

Time: _____

How: ROTARY

Drilling will commence: _____

Reported by: D. HACKFORD-DOGM

Telephone #: _____

Date: 5/6/96 Signed: JLT

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR Wildrose Resources Corporation
ADDRESS 4949 South Albion Street
Littleton, CO 80121

OPERATOR ACCT. NO. N 9660


ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	11915	4304732743	Federal 13-28	NW/SE	28	8S	18E	Uintah	*5/1/96	
WELL 1 COMMENTS: <i>Entity added 5-7-96. LSC</i>											
WELL 2 COMMENTS:											
WELL 3 COMMENTS:											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)


NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)



Kary K. Osterback
Signature
V. P. **5/1/96*
Title Date
Phone No. (303) 770-6566

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT



54.46
Form approved.
Budget Bureau No. 1004-0137
Expires August 31, 1985

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐
b. TYPE OF COMPLETION: NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other _____

2. NAME OF OPERATOR
Wildrose Resources Corp.

3. ADDRESS OF OPERATOR
4949 S. Albion St., Littleton, CO 80121

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface 2007' FSL & 704' FWD (W 73 W)
At top prod. interval reported below same
At total depth same

14. PERMIT NO. 4304732743 DATE ISSUED

5. LEASE DESIGNATION AND SERIAL NO.
U-36442

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME
Federal

9. WELL NO.
13-28

10. FIELD AND POOL, OR WILDCAT
8 mile Flat North

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA
sec. 28, T8S, R18E

12. COUNTY OR PARISH
Utah

13. STATE
Utah

15. DATE SPUDDED 5/1/96 16. DATE T.D. REACHED 5/9/96 17. DATE COMPL. (Ready to prod.) 5/28/96 18. ELEVATIONS (DF, RKB, RT, GB, ETC.)* 4955' GR 19. ELEV. CASINGHEAD 4955'

20. TOTAL DEPTH, MD & TVD 6250' 21. PLUG, BACK T.D., MD & TVD 6053' 22. IF MULTIPLE COMPL., HOW MANY* - 23. INTERVALS DRILLED BY - ROTARY TOOLS 0'-TD CABLE TOOLS No

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5593-5610 Green River 25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN ARI, FDC-CNL, CBL 624-96 27. WAS WELL CORED No

28. CASING RECORD (Report all strings set in well)					
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
8 5/8	24	329'	12 1/4	200 SX (to surface)	-
5 1/2	15.5	6100'	7 7/8	760 SX	-

29. LINER RECORD					30. TUBING RECORD		
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
N/A					2 7/8	5670'	-

31. PERFORATION RECORD (Interval, size and number)		32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.	
5593-5610: 34 holes - 0.45"		DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
		5593-5610	14910 gal x-link gelled water w/ 26,300 # 20/40 sand

33.* PRODUCTION							
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
						Shut-in	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
FLOW. TUBING PRESS.		CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) TEST WITNESSED BY

35. LIST OF ATTACHMENTS
Logs, Daily Reports

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Kay Kattenbreck TITLE V.P. DATE 6/20/96


*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38. GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
				Green River	1758 1758'	1758 1758'
				Wasatch Tongue of Green River	6212'	6212'

DAILY DRILLING REPORT



Operator: Wildrose Resources Corporation
Well: Federal #13-28
T 8 S, R 18 E, Section 28
NW SW (2007' FSL & 704' FWL)
Uintah County, Utah
Projected TD - 6250'
Elevation: GR: 4955', KB: 4965' estimated
Contractor: Union Drilling Company #16

05/02/96 Day 1: TD-349'. Testing BOP's. MI & RU. Spudded @ 1 PM 5/1/96. Drld 17 1/2" hole to 24' KB. Set 14' of 13 3/8" conductor. Drld 12 1/4" hole to 349'. Encountered no water while drlg surface hole. Ran 8 jts (319') of 8 5/8", 24#, J-55 csg w/ guide shoe, insert float & 3 centralizers. Set csg @ 329' KB. RU HOWCO. Pumped 5 BW & 20 bbl gel water. Cemented w/ 200 sx Class 'G' w/ 2% CaCl₂ & 1/4# /sk Flocele. Displaced w/ 19 BW. Had good cement to surface. Bumped plug w/ 780 psi. Float leaking. SI. WOC. Tested BOP's to 2000 psi.

05/03/96 Day 2: TD-1425' drld. Drld 1076' in 14 1/4 hrs w/ air/foam. Ran Bit #3, 7 7/8" SEC S88CF @ 319'. Pulled Bit #3 @ 969'. Bit #3 drld 620' in 6 1/2 hrs. Ran Bit #4 7 7/8" SEC 8SSCF @ 969'. Bit #4 has drld 456' in 7 3/4 hrs. Surveys: 1/2 @ 630', 1 1/4 @ 1182', 1 1/4 @ 1500'.

05/04/96 Day 3: TD-2827' drlg. Drld 1402' in 22 1/2 hrs w/ air/foam. Bit #4 has drld 1858' in 30 1/4 hrs. Surveys: 1 1/2 @ 2050', 1 1/4 @ 2511'.

05/05/96 Day 4: TD-4055' drlg. Drld 1228' in 23 hrs w/ air/foam. Bit #4 has drld 3086' in 53 1/4 hrs. Survey: 1 3/4 @ 3110'.

05/06/96 Day 5: TD-4415' drlg. Drld 360' in 10 1/2 hrs w/ 2% KCl water. Pulled #4 @ 4291'. Bit #4 drld 3322' in 57 1/2 hrs. Ran Bit #5, 7 7/8", HTC ATJ33H @ 4291'. Bit #5 has drld 124' in 6 1/4 hrs.

05/07/96 Day 6: TD-4955' drlg. Drld 540' in 20 1/2 hrs w/ 2% KCl water. Bit #5 has drld 664' in 26 3/4 hrs. Survey: 2 1/4 @ 4675'.

05/08/96 Day 7: TD-5560' drlg. Drld 605' in 2 1/2 hrs w/ 2% KCl water. Bit #5 has drld 1269' in 48 1/4 hrs. Survey: 1 1/2 @ 5175'. Have lost approx 1000 BW since switching to water @ 4291'.

05/09/96 Day 8: TD-6250'. TOH to log. Drld 690' in 22 hrs. w/ 2% KCl water. Rchd TD at 5am 5-9-96. Pulling Bit # 5. Bit # 5 drld 1959' in 70 1/4 hrs.

05/10/96 Day 9: PBTD-6053'. WO Completion. Ran logs using Schlumberger as follows:

ARI 6201'- 330'

FDC-CNL 6249'-4000'

Logger's TD-6251'. Ran 5 1/2" csg as follows:

Float shoe

1 jt 5 1/2", 15.5#, J-55, LTC

Float collar

142 jts 5 1/2", 15.5#, J-55, LTC

w/ 9 centralizers. Set csg @ 6100'. Circulated for 1/2 hr. RU HOWCO. Pumped 5 BW, 2 bbl Super Flush, 5 BW & 20 bbl gel water. Cemented w/ 160 sx HiFill & 600 sx 50/50 Poz w/ 2% gel, 10% salt, 0.5% Halad 322. Displaced w/ 143 bbl 2% KCl water @ 8 BPM. Bumped plug w/ 2600 psi. Plug down @ 3:50 AM 5/10/96. Float held. Pulled up BOP's. Set slips. Released rig @ 6 AM 5/10/96. Drop from report pending completion.

DAILY COMPLETION REPORT

Operator: Wildrose Resources Corporation
Well: Federal #13-28
T 8 S, R 18 E, Section 28
NW SW (2007'' FSL & 704' FWL)
Uintah County, Utah
Elevation: GR: 4955', KB: 4965'
Contractor: Ross Well Service

05/15/96 RU Schlumberger mast truck. Run CBL from 6030' to 4000' & @ cement top @ 1234'. RD Schlumberger.

05/18/96 Day 1: MI & RU Ross Well Service. NUBOP's. SDFN.

05/19/96 Day 2: PBTD-6050'. Unload 200 jts tbg. Ran 4 3/4" bit & scraper on 194 jts tbg to 6050'. Circulate bottoms up w/ 42 bbl 2% KCl water. Pressure tested BOP's & csg to 3500 psi. RU to swab. SWBD FL down to 4500' (95 bbl). POH w/ tbg. RU Schlumberger. Perforated 5593'-5610' (17') w/ 2 JSPF (34 holes) using 4" csg gun. RD Schlumberger. SIFN.

05/20/96 SDF Sunday.

05/21/96 SD - WO Halliburton to frac.

05/22/96 Day 3: CP=25 psi @ 7 AM 5/21/96. Ran Baker Retrievmatic packer on 181 jts 2 7/8" tbg to 5630'. RU HOWCO. Circulated hole w/ 135 bbl heated prepad fluid. Got returns @ 97 bbls. Recovered a few bbls of oil & show of gas. Pulled 1 std tbg. Set packer @ 5565'. Tested backside to 520 psi. Broke down zone w/ 54 bbls heated prepad fluid & 40 ball sealers. Broke @ 2143 psi @ 2 BPM. Increased to 6.5 BPM @ 2700 psi. Saw ball action - max pressure 3130 psi. ISIP=1546 psi, 5 min=1380 psi. Released packer. Ran packer across perms w/ 1 std. POH w/ tbg. RU HOWCO to frac down 5 1/2" csg as follows:

VOLUME	EVENT	RATE	AVERAGE TREATMENT PRESSURE
5526 gal	Pad - 40# Pure Gel III	18 BPM	2450 psi
1982 gal	2-6 ppg 20/40 (35# PG)(8,000#)	24 BPM	2450 psi
7401 gal	6 ppg 20/40 (35#PG)(45,500#)	23 BPM	2250 psi

Well screened out - max pressure - 3700 psi. Frac Volumes: 14,910 gal water, 53,000# 20/40 sand (26,300# in formation, 26,700# in csg)

05/23/96 Day 4: CP=700 psi. Flowed back 10 BLW in 1/2 hr. TIH w/ tbg & circulate @ 1870', 2500', & 3737' w/ heavy sand returns. Tag sand @ 3970'. Circulate sand from 3970'-4200'. Well flowing sand while circulating. Circulated sand @ 4200' for 4 hrs till clean. Ran tbg to 5600' & tagged sand. Circulated out sand to 6050'. Circulate clean. Pulled tbg to 5530'. SIFN. 523 BLWTR.

05/24/96 Day 5: CP=250 psi, TP=250 psi @ 7 AM 5/23/96. Pulled tbg to 4480'. RU to swab. SWBD 130 BLW in 8 hrs. Final FL @ 4000' w/ est oil cut @ 10%. SIFN. 393 BLWTR.

05/25/96 Day 6: CP=55 psi, TP=45 psi. Ran tbg to 5501'. RU to swab. FL @ 4000'. SWBD approx 15 BO & 10 BLW in 3 hrs. FL @ 4300' & gas cut w/ final oil cut est @ 90%. 383 BLWTR. POH w/ tbg. Ran 1 jt tbg, 4' perf sub, SN, 3 jts tbg, tbg anchor, 178 jts tbg. Stripped off BOP's. Set anchor w/ 12,000# tension. BOT @ 5670'. SN @ 5634'. Anchor @ 5537'. SIFN.

05/26/96 Day 7: CP=45 psi, TP=0. Made 2 swab runs. 1st run FL @ 4500'. 2nd run FL @ 4800'. Recovered 4 BO. Flushed tbg w/ 30 bbl hot load water. Started to run rods - changed orders. POH w/ 67-3/4" rods. RU to swab. SWBD back 32 BLW plus 20 BO in 3 hrs. FL @ 5600' w/ 90% oil cut. Waited 1/2 hr - made swab run - 50'(0.3611 bbl) of entry - 95% oil. SIFN. 381 BLWTR. SWBD total of 39 BO in 3 days.

05/27-28/96 SDF Memorial Day.

DAILY COMPLETION REPORT

Operator: Wildrose Resources Corporation
Well: Federal #13-28
T 8 S, R 18 E, Section 28
NW SW (2007'' FSL & 704' FWL)
Uintah County, Utah
Elevation: GR: 4955', KB: 4965'
Contractor: Ross Well Service

Page 2

05/29/96 Day 8: CP=250 psi, TP=0 @ 7 AM 5/28/96. FL @ 4500'. SWBD approx 10 BO & 2 BLW in 4 runs. FL @ 5600'. Waited 1/2 hr - made swab run - no entry. Wait 1/2 hr - made swab run - no entry. Lay down rods in derrick. SI tbg w/ ball valve. RD & MO Ross Well Service. Reservoir appears to be non-commercially productive due to the lack of permeability.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator: Wildrose Resources Corporation

3. Address and Telephone Number:
3121 Cherryridge Road, Englewood, CO 80110 PH: 303-761-9965

4. Location of Well

Footage: 2007' FSL & 704' FWL
QQ, Sec., T., R., M.: NW/SW Section 28, T8S, R18E

5. Lease Designation and Serial Number:

U-36442

6. If Indian, Allottee or Tribe Name:

7. Unit Agreement Name:

8. Well Name and Number:

Federal #13-28

9. API Well Number:

43-047-32743

10. Field and Pool, or Wildcat:

Eight Mile Flat North

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)

- | | |
|---|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other Well Status | |

Approximate date work will start _____

SUBSEQUENT REPORT (Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The 13-28 well was completed in 1996 but was not put on pump as swab tests indicated that low pressure and permeability would make it uneconomical to pump. The 13-28 well offsets three other Wildrose wells and this area was projected for a Wildrose waterflood project during 1998. Due to low oil prices this waterflood project has been delayed. Therefore, the 13-28 well has not been plugged as it may be used as part of the secondary recovery project.

This well was cased with new 15.5# casing in 1996 and cemented back to 1200'. With the low pressures and permeability indicated during completion, the oil fluid level will be below 4000', which is well below the cement top. Therefore, we believe this well has mechanical integrity and is no threat to public health, safety or the environment.

Therefore, Wildrose requests an approval of extension of the current well status.

13.

Name & Signature:

Kary J. Kattenbacher
Kary J. Kattenbacher

Title:

V.P.

Date: 3/25/99

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Date: 4-1-99

By: RSH

(404)

COPY SENT TO OPERATOR

Date:

Initials:

5-4-99
CJP

(See Instructions on Reverse Side)




EXHIBIT "A"
Attached to Sundry Notices

Wildrose Resources Corporation
and
Inland Production Company

Unit	API	Well	Comp.	Elev	Loc.	S	1/4 1/4	Twp	Rng	Co	Lease	Type
N	4304731528	REX LAMB 34-1	WR	4932* GR	2116 FNL 2132 FEL	34	SWNE	040S	010E	UTA	FEE	OW
N	4304731692	REX LAMB 34-2	WR	4932* GR	2018 FNL 1068 FEL	34	SENE	040S	010E	UTA	FEE	OW
N	4301331914	HARBOURTOWN FED 21-33	WR	5129* GR	0513 FNL 1938 FWL	33	NENW	080S	170E	DU	U-71368	OW
N	4301331915	HARBOURTOWN FED 42-33	WR	5128* GR	1954 FNL 0851 FEL	33	SENE	080S	170E	DU	U-71368	OW
N	4301331916	HARBOURTOWN FED 23-34	WR	5088* GR	1943 FSL 2162 FWL	34	NESW	080S	170E	DU	U-71368	OW
N	4301331917	HARBOURTOWN FED 44-34	WR	5063* GL	0835 FSL 0500 FEL	34	SESE	080S	170E	DU	U-71368	OW
N	4304732080	FEDERAL #23-26	WR	4910* KB	2113 FSL 1844 FWL	26	NESW	080S	180E	UTA	U-36442	OW
N	4304732700	FEDERAL 24-26	WR	4913* GR	0660 FSL 1980 FWL	26	SESW	080S	180E	UTA	U-36442	OW
N	4304732720	FEDERAL 13-26	WR	4905* GR	2018 FSL 0832 FWL	26	NWSW	080S	180E	UTA	U-36442	OW
N	4304732731	FEDERAL 12-26	WR	4924* GR	2956 FSL 0470 FWL	26	SWNW	080S	180E	UTA	U-36442	GW
N	4304732847	FEDERAL 34-26	WR	4907* GR	0741 FSL 1957 FEL	26	SWSE	080S	180E	UTA	U-75532	OW
N	4304732732	FEDERAL 43-27	WR	4862* GR	1917 FSL 0559 FEL	27	NESE	080S	180E	UTA	U-36442	OW
N	4304732733	FEDERAL 14-28	WR	4902* GR	0860 FSL 0846 FWL	28	SWSW	080S	180E	UTA	U-51081	OW
N	4304732743	FEDERAL 13-28	WR	4955* GR	2007 FSL 0704 FWL	28	NWSW	080S	180E	UTA	U-36442	OW
N	4304731464	PARIETTE FED 10-29	WR	4890* GR	1843 FSL 2084 FEL	29	NWSE	080S	180E	UTA	U-51081	OW
N	4304731550	W PARIETTE FED 6-29	WR	4892* GR	1978 FNL 2141 FWL	29	SENW	080S	180E	UTA	U-36846	OW
N	4304732079	FEDERAL 44-29	WR	4993* KB	0660 FSL 0660 FEL	29	SESE	080S	180E	UTA	U-51081	OW
N	4304732701	FEDERAL 43-29	WR	4886* GR	1904 FSL 0710 FEL	29	NESE	080S	180E	UTA	U-51081	OW
N	4304732742	FEDERAL 34-29	WR	4917* GR	0712 FSL 1925 FEL	29	SWSE	080S	180E	UTA	U-51081	OW
N	4304732848	PARIETTE FED 32-29	WR	4870* GR	1942 FNL 1786 FEL	29	SWNE	080S	180E	UTA	U-36846	OW
N	4304731116	NGC ST 33-32	WR	4930* GR	1914 FSL 1911 FEL	32	NWSE	080S	180E	UTA	ML-22058	OW
N	4304732077	FEDERAL 12-34	WR	4845* KB	1571 FNL 0375 FWL	34	SWNW	080S	180E	UTA	U-51081	OW
N	4304732702	FEDERAL 42-35	WR	4815* GR	1955 FNL 0463 FEL	35	SENE	080S	180E	UTA	U-51081	OW
N	4304732721	FEDERAL 43-35	WR	4870* GR	2077 FSL 0696 FEL	35	NESE	080S	180E	UTA	U-49430	OW
N	4304731345	GULF STATE 36-13	WR	4831* GR	1850 FSL 0600 FWL	36	NWSW	080S	180E	UTA	ML-22057	OW
N	4304731350	GULF STATE 36-11	WR	4837* GR	0677 FNL 0796 FWL	36	NWNW	080S	180E	UTA	ML-22057	OW
N	4304731864	GULF STATE 36-12	WR	4882* GR	1778 FNL 0782 FWL	36	SWNW	080S	180E	UTA	ML-22057	OW
N	4304731892	GULF STATE 36-22	WR	4923* GR	1860 FNL 1980 FWL	36	SENW	080S	180E	UTA	ML-22057	OW
N	4304732580	UTD STATE 36-K	WR	4809* GR	2120 FSL 1945 FWL	36	NESW	080S	180E	UTA	ML-22057	OW
N	4304732581	UTD STATE 36-M	WR	4744* KB	0848 FSL 0648 FWL	36	SWSW	080S	180E	UTA	ML-22057	OW
N	4304731415	WILDROSE FEDERAL 31-1	WR	4871* GR	2051 FSL 0683 FWL	31	NWSW	080S	190E	UTA	U-30103	OW
N	4301330642	MONUMENT BUTTE 1-3	WR	5156* GR	1945 FSL 0816 FWL	03	NWSW	090S	170E	DU	U-44004	OW
N	4301330810	MONUMENT BUTTE 2-3	WR	5107* GR	1918 FNL 1979 FWL	03	SENW	090S	170E	DU	U-44004	OW
N	4301331760	PINEHURST FEDERAL 3-7	WR	5096* GR	2062 FNL 1999 FEL	03	SWNE	090S	170E	DU	61252	OW
N	4301331761	PINEHURST FEDERAL 3-8	WR	5030* GR	1980 FNL 0660 FEL	03	SENE	090S	170E	DU	61252	OW
N	4301331764	RIVIERA FEDERAL 3-11	WR	5123* GR	2050 FSL 2008 FWL	03	NESW	090S	170E	DU	U-44004	OW
N	4301332183	RIVIERA FED 3-9	WR	5030 GR	1922 FSL 0605 FEL	03	NESE	090S	170E	DU	U-44004	OW
N	4301332184	RIVIERA FED 3-10	WR	5108 GR	2100 FSL 2190 FEL	03	NWSE	090S	170E	DU	U-44004	OW
N	4301331023	FEDERAL 15-1-B	WR	5177* GR	0660 FNL 1983 FEL	15	NWNE	090S	170E	DU	U-44429	OW
N	4304732777	BIRKDALE FED 13-34	WR	5067* GR	1768 FSL 0615 FWL	34	NWSW	090S	180E	UTA	U-68618	OW

END OF EXHIBIT

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budgeted Bureau No. 1004-0135
Expires March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas well ☐ Other


2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

1401 17TH STREET, SUITE 1000, DENVER, CO 80202 (303)893-0102

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)



5. Lease Designation and Serial No.

See Attached Exhibit

6. If Indian, Allottee or Tribe Name

7. If unit or CA, Agreement Designation

8. Well Name and No.

See Attached Exhibit

9. API Well No.

See Attached Exhibit

10. Field and Pool, or Exploratory Area

11. County or Parish, State

Uintah Co., Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing repair
☐ Altering Casing
☒ Other Change of Operator
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work)

Effective 4/15/04, Inland Production Company, as Contract Operator, will take over operations of the attached referenced wells. The previous operator was:

Wildrose Resources Corporation
3121 Cherryridge Road
Englewood, Colorado 80110-6007

Effective 4/15/04, Inland Production Company, as Contract Operator, is responsible under the terms and conditions of the leases for operations conducted on the leased lands or a portion thereof under BLM Bond No. UT0056 issued by Hartford.

I hereby certify that the foregoing is true and correct. (Current Contract Operator)

Signed

Bill I. Pennington
Bill I. Pennington

Title

President, Inland Production Company

Date

4/15/04

(This space of Federal or State office use.)

Approved by

Kirk Fulwood

Title

Petroleum Engineer

Date

5/20/04

Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly to make to any department of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

FORM 9

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached Exhibit
2. NAME OF OPERATOR: Inland Production Company <i>N5160</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1401 17th St. #1000 CITY <i>Denver</i> STATE <i>Co</i> ZIP <i>80202</i>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: See Attached Exhibit
QTR/CTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER:
COUNTY:		10. FIELD AND POOL, OR WILDCAT:
STATE: <i>UTAH</i>		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective 4/15/04, Inland Production Company, as Contract Operator, will take over operations of the attached referenced wells. The previous operator was:

Wildrose Resources Corporation *N9660*
3121 Cherryridge Road
Englewood, Colorado 80110-6007

Effective 4/15/04, Inland Production Company, as Contract Operator, is responsible under the terms and conditions of the leases for operations conducted on the leased lands or a portion thereof under BLM Bond No. UT0056 issued by Hartford.

Attached is a list of wells included.

Previous Operator Signature:

Title:

NAME (PLEASE PRINT) <i>Marc MacAluso</i>	TITLE <i>CEO, Wildrose Resources Corporation</i>
SIGNATURE <i>[Signature]</i>	DATE <i>4/15/04</i>

(This space for State use only)

RECEIVED

APR 26 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS <small>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</small>		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached Exhibit
1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: _____
2. NAME OF OPERATOR: Inland Production Company N5160		7. UNIT or CA AGREEMENT NAME: _____
3. ADDRESS OF OPERATOR: 1401 17th St. #1000 CITY Denver STATE Co ZIP 80202		8. WELL NAME and NUMBER: See Attached Exhibit
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ COUNTY: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____ STATE: UTAH		9. API NUMBER: _____
10. FIELD AND POOL OR WILDCAT: _____		11. PHONE NUMBER: (303) 893-0102

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT <small>(Submit in Duplicate)</small> <small>Approximate date work will start:</small> _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input checked="" type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input type="checkbox"/> SUBSEQUENT REPORT <small>(Submit Original Form Only)</small> <small>Date of work completion:</small> _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective 4/15/04, Inland Production Company, as Contract Operator, will take over operations of the attached referenced wells. The previous operator was:

Wildrose Resources Corporation
3121 Cherryridge Road
Englewood, Colorado 80110-6007

Effective 4/15/04, Inland Production Company, as Contract Operator, is responsible under the terms and conditions of the leases for operations conducted on the leased lands or a portion thereof under BLM Bond No. UT0056 issued by Hartford.

Attached is a list of wells included.

Current Contract Operator Signature: _____

Title: _____

NAME (PLEASE PRINT) Bill I. Pennington	TITLE President, Inland Production Company
SIGNATURE <i>Bill I. Pennington</i>	DATE 4/15/04

(This space for State use only)

(5/2000)

(See instructions on Reverse Side)

RECEIVED
APR 26 2004
DIV. OF OIL, GAS & MINING

EXHIBIT "A"
Attached to Sundry Notices

**Wildrose Resources Corporation
and
Inland Production Company**

N	4304731528	REX LAMB 34-1	WR	4932° GR	2116 FNL 2132 FEL	34	SWNE	040S	010E	UTA	FEE	OW
N	4304731692	REX LAMB 34-2	WR	4932° GR	2018 FNL 1088 FEL	34	SENE	040S	010E	UTA	FEE	OW
N	4301331914	HARBOUR TOWN FED 21-33	WR	5129° GR	0613 FNL 1938 FWL	33	NENW	080S	170E	DU	U-71368	OW
N	4301331915	HARBOUR TOWN FED 42-33	WR	5128° GR	1954 FNL 0851 FEL	33	SENE	080S	170E	DU	U-71368	OW
N	4301331916	HARBOUR TOWN FED 23-34	WR	5088° GR	1943 FSL 2162 FWL	34	NESW	080S	170E	DU	U-71368	OW
N	4301331917	HARBOUR TOWN FED 44-34	WR	5063° GL	0835 FSL 0500 FEL	34	SESE	080S	170E	DU	U-71368	OW
N	4304732080	FEDERAL #23-26	WR	4910° KB	2113 FSL 1844 FWL	26	NESW	080S	180E	UTA	U-36442	OW
N	4304732700	FEDERAL 24-26	WR	4913° GR	0860 FSL 1980 FWL	26	SESW	080S	180E	UTA	U-36442	OW
N	4304732720	FEDERAL 13-26	WR	4905° GR	2018 FSL 0832 FWL	26	NWSW	080S	180E	UTA	U-36442	OW
N	4304732731	FEDERAL 12-26	WR	4924° GR	2956 FSL 0470 FWL	26	SWNW	080S	180E	UTA	U-36442	GW
N	4304732847	FEDERAL 34-26	WR	4907° GR	0741 FSL 1957 FEL	26	SWSE	080S	180E	UTA	U-75532	OW
N	4304732732	FEDERAL 43-27	WR	4862° GR	1917 FSL 0559 FEL	27	NESE	080S	180E	UTA	U-36442	OW
N	4304732733	FEDERAL 14-28	WR	4902° GR	0860 FSL 0846 FWL	28	SWSW	080S	180E	UTA	U-51081	OW
N	4304732743	FEDERAL 13-28	WR	4955° GR	2007 FSL 0704 FWL	28	NWSW	080S	180E	UTA	U-36442	OW
N	4304731464	PARIETTE FED 10-29	WR	4890° GR	1843 FSL 2084 FEL	29	NWSE	080S	180E	UTA	U-51081	OW
N	4304731550	W PARIETTE FED 6-29	WR	4892° GR	1978 FNL 2141 FWL	29	SENW	080S	180E	UTA	U-36846	OW
N	4304732079	FEDERAL 44-29	WR	4993° KB	0660 FSL 0660 FEL	29	SESE	080S	180E	UTA	U-51081	OW
N	4304732701	FEDERAL 43-29	WR	4886° GR	1904 FSL 0710 FEL	29	NESE	080S	180E	UTA	U-51081	OW
N	4304732742	FEDERAL 34-29	WR	4917° GR	0712 FSL 1928 FEL	29	SWSE	080S	180E	UTA	U-51081	OW
N	4304732848	PARIETTE FED 32-29	WR	4870° GR	1942 FNL 1786 FEL	29	SWNE	080S	180E	UTA	U-36846	OW
N	4304731118	NGC ST 33-32	WR	4930° GR	1914 FSL 1911 FEL	32	NWSE	080S	180E	UTA	ML-22058	OW
N	4304732077	FEDERAL 12-34	WR	4845° KB	1571 FNL 0375 FWL	34	SWNW	080S	180E	UTA	U-51081	OW
N	4304732702	FEDERAL 42-35	WR	4815° GR	1955 FNL 0463 FEL	35	SENE	080S	180E	UTA	U-51081	OW
N	4304732721	FEDERAL 43-35	WR	4870° GR	2077 FSL 0896 FEL	35	NESE	080S	180E	UTA	U-49430	OW
N	4304731345	GULF STATE 36-13	WR	4831° GR	1850 FSL 0600 FWL	36	NWSW	080S	180E	UTA	ML-22057	OW
N	4304731350	GULF STATE 36-11	WR	4837° GR	0677 FNL 0796 FWL	36	NWNW	080S	180E	UTA	ML-22057	OW
N	4304731854	GULF STATE 36-12	WR	4882° GR	1778 FNL 0782 FWL	36	SWNW	080S	180E	UTA	ML-22057	OW
N	4304731892	GULF STATE 36-22	WR	4923° GR	1860 FNL 1980 FWL	36	SENW	080S	180E	UTA	ML-22057	OW
N	4304732580	UTD STATE 36-K	WR	4809° GR	2120 FSL 1945 FWL	36	NESW	080S	180E	UTA	ML-22057	OW
N	4304732581	UTD STATE 36-M	WR	4744° KB	0848 FSL 0648 FWL	36	SWSW	080S	180E	UTA	ML-22057	OW
N	43047371415	WILDROSE FEDERAL 31-1	WR	4871° GR	2051 FSL 0683 FWL	31	NWSW	080S	190E	UTA	U-30103	OW
N	4301330642	MONUMENT BUTTE 1-3	WR	5156° GR	1945 FSL 0816 FWL	03	NWSW	090S	170E	DU	U-44004	OW
N	4301330810	MONUMENT BUTTE 2-3	WR	5107° GR	1918 FNL 1979 FWL	03	SENW	090S	170E	DU	U-44004	OW
N	4301331760	PINEHURST FEDERAL 3-7	WR	5096° GR	2062 FNL 1999 FEL	03	SWNE	090S	170E	DU	61252	OW
N	4301331761	PINEHURST FEDERAL 3-8	WR	5030° GR	1980 FNL 0660 FEL	03	SENE	090S	170E	DU	61252	OW
N	4301331764	RIVIERA FEDERAL 3-11	WR	5123° GR	2050 FSL 2008 FWL	03	NESW	090S	170E	DU	U-44004	OW
N	4301332183	RIVIERA FED 3-9	WR	5030 GR	1922 FSL 0605 FEL	03	NESE	090S	170E	DU	U-44004	OW
N	4301332184	RIVIERA FED 3-10	WR	5108 GR	2100 FSL 2190 FEL	03	NWSE	090S	170E	DU	U-44004	OW
N	4301331023	FEDERAL 15-1-B	WR	5177° GR	0660 FNL 1983 FEL	15	NWNE	090S	170E	DU	U-44429	OW
N	4304732777	BIRKDALE FED 13-34	WR	5067° GR	1768 FSL 0615 FWL	34	NWSW	090S	180E	UTA	U-68618	OW

END OF EXHIBIT

RECEIVED
APR 26 2004
DIV. OF OIL, GAS & MINING

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

4/15/2004

FROM: (Old Operator):	TO: (New Operator):
N9660-Wildrose Resources Corporation 3121 Cherryridge Road Englewood, CO 80110-6007 Phone: 1-(303) 761-9965	N5160-Inland Production Company 1401 17th St, Suite 1000 Denver, CO 80202 Phone: 1-(303) 893-0102

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
HARBOURTOWN FED 21-33	33	080S	170E	4301331914	✓ 12304	Federal	P	OW	
HARBOURTOWN FED 42-33	33	080S	170E	4301331915	✓ 12310	Federal	P	OW	
HARBOURTOWN FED 23-34	34	080S	170E	4301331916	✓ 12320	Federal	P	OW	C
HARBOURTOWN FED 44-34	34	080S	170E	4301331917	✓ 12321	Federal	P	OW	
FEDERAL #23-26	26	080S	180E	4304732080	✓ 11265	Federal	P	OW	
FEDERAL 24-26	26	080S	180E	4304732700	✓ 11808	Federal	P	OW	
FEDERAL 13-26	26	080S	180E	4304732720	✓ 11832	Federal	P	OW	
FEDERAL 12-26	26	080S	180E	4304732731	✓ 11896	Federal	P	GW	
FEDERAL 34-26	26	080S	180E	4304732847	✓ 12123	Federal	P	OW	
FEDERAL 43-27	27	080S	180E	4304732732	✓ 11903	Federal	S	OW	
FEDERAL 14-28	28	080S	180E	4304732733	✓ 11908	Federal	S	OW	
FEDERAL 13-28	28	080S	180E	4304732743	✓ 11915	Federal	TA	OW	
PARIETTE FED 10-29	29	080S	180E	4304731464	✓ 1428	Federal	P	OW	
W PARIETTE FED 6-29	29	080S	180E	4304731550	✓ 9905	Federal	S	OW	
FEDERAL 44-29	29	080S	180E	4304732079	✓ 11267	Federal	S	OW	
FEDERAL 43-29	29	080S	180E	4304732701	✓ 11816	Federal	P	OW	
FEDERAL 34-29	29	080S	180E	4304732742	✓ 11918	Federal	P	OW	
PARIETTE FED 32-29	29	080S	180E	4304732848	✓ 12144	Federal	P	OW	
FEDERAL 12-34	34	080S	180E	4304732077	✓ 11276	Federal	S	OW	
FEDERAL 42-35	35	080S	180E	4304732702	✓ 11811	Federal	S	OW	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 4/26/2004
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on 4/26/2004
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 12/10/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 755627-0143
5. If **NO**, the operator was contacted contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: applied for

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC"** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 4/28/2004
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 4/28/2004
3. Bond information entered in RBDMS on: 4/28/2004
4. Fee wells attached to bond in RBDMS on: 4/28/2004
5. Injection Projects to new operator in RBDMS on: n/a
6. Receipt of Acceptance of Drilling Procedures for APD/New on: 4/28/2004

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: 4021509 Wildrose

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: n/a

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number RN4471290
2. The FORMER operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 4/28/2004

COMMENTS:



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Vernal Field Office

170 South 500 East

Vernal, UT 84078

(435) 781-4400 Fax: (435) 781-4410
<http://www.blm.gov/utah/vernal>



IN REPLY REFER TO:

3162.3

UT08300

May 21, 2004

Bill I. Pennington
Inland Production Company
1401 17th Street, Suite 1000
Denver, Colorado 80202

Re: Wells: Federal 12-26,
SWNW, Sec. 26, T8S, R18E
Federal 13-26,
NWSW, Sec. 26, T8S, R18E
Federal 23-26,
NESW, Sec. 26, T8S, R18E
Federal 24-26,
SESW, Sec. 26, T8S, R18E
Federal 43-27,
NESE, Sec. 27, T8S, R18E
Federal 13-28,
NWSW, Sec. 28, T8S, R18E
Uintah County, Utah
Lease No. U-36442

Dear Mr. Pennington:

This correspondence is in regard to the self-certification statement submitted requesting a change in operator for the referenced wells. After a review by this office, the change in operator request is approved. Effective immediately, Inland Production Company is responsible for all operations performed on the referenced wells. All liability will now fall under your bond, BLM Bond No. UT0056, for all operations conducted on the referenced wells on the leased land.

Our records show that a right-of-way, UTU-65194, has been issued for the off lease portion of the pipeline for the Federal 23-26 well. In order for Inland Production Company to obtain the Bureau of Land Management's approval for the use of this right-of-way, you must have this right-of-way assigned over to Inland Production Company. Please contact Cindy McKee at 435-781-4434 for instructions on how to complete the assignment of the right-of-way.

If you have any other questions concerning this matter, please contact Leslie Walker of this office at (435) 781-4497.

Sincerely,

Kirk Fleetwood
Petroleum Engineer

cc: UDOGM
Wildrose Resources Corp.

RECEIVED
MAY 27 2004
DIV. OF OIL, GAS & MINING



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, UT 84145-0155

<http://www.blm.gov>



IN REPLY REFER TO:

3106

(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office

From: Acting Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		

1. GLH

3. FILE

Designation of Agent/Operator

Merger

9/1/2004

TO: (New Operator):
N2695-Newfield Production Company
Route 3 Box 3630
Myton, UT 84052
Phone: 1-(435) 646-3721

Unit:

[illegible]

5. If **NO**, the operator was contacted contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 2/28/2005
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

SUBMIT IN TRIPLICATE - Other Instructions on page 2

1. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-36442
2. Name of Operator NEWFIELD PRODUCTION COMPANY		6. If Indian, Allottee or Tribe Name.
3a. Address Route 3 Box 3630 Myton, UT 84052	3b. Phone (include area code) 435.646.3721	7. If Unit or CA/Agreement, Name and/or
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 2007 FSL 704 FWL NWSW Section 28 T8S R18E		8. Well Name and No. FEDERAL 13-28
		9. API Well No. 4304732743
		10. Field and Pool, or Exploratory Area MONUMENT BUTTE
		11. County or Parish, State UINTAH, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input checked="" type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield will place the subject well on production by October 15, 2007. Plans are in place to construct a tank battery and place necessary production equipment on the well as well as open additional pay intervals in the Green River formation. The intervals to be opened are as follows:

4594-4602, 4964-4972, 5593-5610 (re-perforate), 5888-5494, & 5924-5940.

All intervals will be shot with 4JSPF and fracture stimulated.

I hereby certify that the foregoing is true and correct (Printed/ Typed) Chris Clark		Title Production Engineer	
Signature 		Date 07/06/2007	
THIS SPACE FOR FEDERAL OR STATE OFFICE USE			
Approved by: _____		Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		Office	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction.			

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-36442

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

8. WELL NAME and NUMBER:
FEDERAL 13-28

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

9. API NUMBER:
4304732743

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

10. FIELD AND POOL, OR WILDCAT:
MONUMENT BUTTE

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 2007 FSL 704 FWL

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NWSW, 28, T8S, R18E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will

☒ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of Work Completion:

10/02/2008

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/STOP)

☐ RECLAMATION OF WELL SITE

☒ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLAIR

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: -

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was recompleted and then placed back on production, attached is a daily status report. The following perforations were added in the Green River Formation:

GB6 4594'-4602' 4 JSPF 32 holes

DS2 4964'-4972' 4 JSPF 32 holes

D2 5090'-5100' 4 JSPF 40 holes

A3 5593'-5610' reperf

CP1 5888'-5894' 4 JSPF 24 holes

CP2 5924'-5940' 4 JSPF 64 holes

NAME (PLEASE PRINT) Jentri Park

TITLE Production Tech

SIGNATURE

DATE 10/29/2008

(This space for State use only)

RECEIVED

NOV 03 2008

DIV. OF OIL, GAS & MINING

Daily Activity Report

Format For Sundry

FEDERAL 13-28-8-18**7/1/2008 To 11/30/2008****9/24/2008 Day: 1****Recompletion**

Western #2 on 9/23/2008 - MIRU Western #2. Bleed pressure off casing. ND wellhead & release TA @ 5536'. NU BOP. Talley, PU & TIH W/ 13 jts work string to tag PBTD @ 6053' (no fill). LD work string. RU HO trk to tbg. Fill W/ 10 BW, pressured up to 1000 psi, then broke loose. Pump 70 BW total @ 250°F. Returned 40 BW. SIFN W/ est 70 BWTR.

9/25/2008 Day: 2**Recompletion**

Western #2 on 9/24/2008 - RU HO trk & circulate oil f/ well W/ 130 BW @ 250°F. Rec add'l 20 BO. TOH & talley production tbg--LD BHA. RU Perforators LLC WLT & packoff. Perf & re-perf intervals W/ 3 1/8" slick guns as follows: CP2 sds @ 5924-40' (new); CP1 sds @ 5888-94' (new); A3 sds @ 5593-5610' (re-perf); D2 sds @ 5090-5100' (new); DS2 sds @ 4964-72' (new) & GB6 sds @ 4594-4602' (new). All 4 JSPF in 3 runs total. RD WLT. Talley, PU & TIH W/ Weatherford 5 1/2" "TS" RBP, RH, tbg sub, 5 1/2" "HD" pkr & 2 7/8 8rd 6.5# N-80 tbg. Set plug @ 5909' & pkr @ 5857'. Pressure up against CP1 perfs (5888-94') to 5000 psi. Work pressure back & forth several times W/ no leakoff. Release pkr & RIH to place EOT @ 5899'. Spot 55 gals 15% HCL acid across perfs. Pull pkr to 5857' & re-set. Pressure against perfs to 5000 psi. Still no leakoff. Leave pressure against perfs & SIFN. Est 70 BWTR.

9/26/2008 Day: 3**Recompletion**

Western #2 on 9/25/2008 - RU BJ Services. Broke CP1 sds down @ 4080 psi to 1550 psi w/ 3 bbls. Released tools. Reset RBP @ 6000' w/ pkr @ 5903'. RU BJ & break CP2 sds down @ 6800 psi w/ 3 bbls fluid communicated. Released pkr & reset @ 5890'. Still circulates. Reset in couple different places. TOOH w/ tbg. RU different "HD" pkr. TIH w/ tbg. Set pkr @ 5960'. Test tools. Released pkr & set @ 5768'. Pressure casing to 100 psi & held during frac. RU BJ & frac CP2 & CP1 sds down tbg w/ 45,122#'s of 20/40 sand in 425 bbls of :Lightning 17 frac fluid. Perfs broke down @ 2406 psi. Pump 30 gals of Techna Hib chemical @ 4% by volume. Treated @ ave pressure of 3131 @ ave rate of 14.7 bpm w/ 6 ppg of sand. ISIP was 1472. Flow well back. Well flowed for 1.5 hours & died w/ 240 bbls rec'd w/ 4000#'s sand. Released pkr & circulate tbg clean. TIH w/ tbg to tag 30' of sand. C/O to RBP & released. TOOH w/ tbg to reset RBP @ 5660'. Leave pkr hang @ 5457'. SIFN.

9/27/2008 Day: 4**Recompletion**

Western #2 on 9/26/2008 - Set pkr @ 5448'. Pressure casing to 500 psi & held during frac. RU BJ & frac stage #2, A3 sds down tbg w/ 15,025#'s of 20/40 sand in 382 bbls of :Lightning 17 frac fluid. Perfs broke down @ 3688 psi. Pump 30 gals of Techna Hib chemical @ 4% by volume. Treated @ ave pressure of 5638 @ ave rate of 14.6 bpm w/ 6 ppg of sand. Screened out frac w/ 10,047 in perfs w/ 4# on perfs w/ 4978#'s in tbg. No flow back. Released pkr & circulate tbg clean. TIH w/ tbg to tag 50' of sand. C/O to RBP & released. TOOH w/ tbg. Set RBP @ 5167'. Set pkr @ 5126'. Test tbg to 2500 psi. Release pkr & reset @ 5017'. RU BJ & perfs won't break down. Release pkr. TIH w/ tbg to spot 55 gals of 15% HCL on perfs. Reset pkr @ 5017'. Pressure casing to 500 psi & held during frac. RU BJ & frac stage #3, D2 sds down tbg w/ 55,043#'s of 20/40 sand in 476 bbls of :Lightning 17 frac fluid. Perfs broke

down @ 2272 psi. Pump 30 gals of Techna Hib chemical @ 4% by volume. Treated @ ave pressure of 3599 @ ave rate of 14.4 bpm w/ 6 ppg of sand. ISIP was 1915. Flow well back. Well flowed for 1.5 hours & died w/ 300 bbls rec'd (2500#'s). Pressure casing to 500 psi. Released pkr & circulate tbg clean. TIH w/ tbg to tag 35' of sand. C/O to RBP & released. TOOH w/ tbg. Set RBP @ 5030'. Set pkr @ 5000'. Test tbg to 2500 psi. Release pkr & reset @ 4849'. Pressure casing to 500 psi & held during frac. RU BJ & frac stage #4, DS2 sds down tbg w/ 35,022#'s of 20/40 sand in 341 bbls of :Lightning 17 frac fluid. Perfs broke down @ 1436 psi. Pump 30 gals of Techna Hib chemical @ 4% by volume. Treated @ ave pressure of 3729 @ ave rate of 16 bpm w/ 6 ppg of sand. ISIP was 1983. Flow well back. Well flowed for 1 hours & died w/ 150 bbls rec'd (3000#'s) show of oil & gas. Pressure casing to 500 psi. Released pkr & circulate tbg clean. TIH w/ tbg to tag 35' of sand. C/O to RBP & released. TOOH w/ tbg. Set RBP @ 4650'. Set pkr @ 4471'. Pressure casing to 500 psi & held during frac. RU BJ & frac stage #5, GB6 sds down tbg w/ 22,569#'s of 20/40 sand in 241 bbls of :Lightning 17 frac fluid. Perfs broke down @ 4600 psi. Pump 30 gals of Techna Hib chemical @ 4% by volume. Treated @ ave pressure of 3994 @ ave rate of 16 bpm w/ 6 ppg of sand. ISIP was 1908. Flow well back. Well flowed for 1 hours & died w/ 150 bbls rec'd (2500#'s). Pressure casing to 500 psi. Open unloader valve on pkr & circulate tbg clean. Close unloader valve & SIFN.

9/30/2008 Day: 5

Recompletion

Western #2 on 9/29/2008 - Open well w/ 300 psi on tbg. Pressure casing to 500 psi. Released pkr. Circulate tbg clean. TIH w/ tbg to tag 20' of sand. C/O to RBP @ 4650'. Released RBP. TIH w/ tbg & set RBP @ 6000'. TOOH w/ tbg to leave EOT @ 4481'. RU swab equipment. Made 14 runs & rec'd 146 bbls fluid. Last run showed trace of oil w/ no sand. FFL was 1200'. RD swab equipment. TIH w/ tbg to tag sand (2'). Released RBP. Circulate well clean to PBTD @ 6053'. TOOH w/ tbg. LD tools. SIFN.

10/1/2008 Day: 6

Recompletion

Western #2 on 9/30/2008 - Open well w/ 0 psi on tbg. TIH w/ bull plug, 2 jts tbg, 2-7/8" nipple, PBGA, 1 jt tbg, SN, 2 jts tbg, TA new CDI w/ 45,000# shear, 186 jts tbg. Test tbg 3 time going in hole. RU swab equipment. Retrieve standin valve. RD BOP's. Set TA @ 5783' w/ 16,000#'s tension w/ SN @ 5817' & EOT @ 5917'. Flush tbg w/ 60 bbls water. Pickup & prime pump. TIH w/ 2-1/2" x 1- 3/4" x 20' x 20.5' new CDI RHAC pump w/ 186"SL, 6- 1-1/2" weight rods, 20- 3/4" guided rods, 106- 3/4" plain rods, 100- 7/8" guided rods, 2', 8' x 7/8" pony rod, 1-1/2" x 26" polished rod. Space pump. Test tbg & pump to 800 psi. RDMOSU. SIFN. Left unit down due to surface equipment.

10/2/2008 Day: 7

Recompletion

Western #2 on 10/1/2008 - Repair surface equipment & PWOP @ 4:00 pm, w/ 72" SL, @ 6 SPM. FINAL REPORT!

Pertinent Files: Go to File List

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-36442
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630, Myton, UT, 84052		8. WELL NAME and NUMBER: FEDERAL 13-28
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2007 FSL 0704 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSW Section: 28 Township: 08.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047327430000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 6/30/2014	<input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> DRILLING REPORT Report Date:	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <p>The subject well has been converted from a producing oil well to an injection well on 06/30/2014. Initial MIT on the above listed well. On 06/30/2014 the casing was pressured up to 1539 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not an EPA representative available to witness the test. EPA# UT22197-10513</p>		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto		PHONE NUMBER 435 646-4874
SIGNATURE N/A		TITLE Water Services Technician
DATE 7/2/2014		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY July 02, 2014

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 6 130 114
Test conducted by: Brendan Curry
Others present: _____

Well Name: <u>Federal 13-28</u>	Type: <u>ER SWD</u>	Status: <u>AC TA UC</u>
Field: <u>Greater monument Butte</u>		
Location: <u>13</u>	Sec: <u>28</u>	T <u>8</u> N <u>18</u> R <u>18</u> B/W County: <u>Uintah</u> State: <u>UT</u>
Operator: <u>Newfield Production Company</u>		
Last MIT: <u>1</u>	Maximum Allowable Pressure: _____	PSIG

Is this a regularly scheduled test? ☐ Yes ☒ No
Initial test for permit? ☒ Yes ☐ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0/0 psig

MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING	PRESSURE		
Initial Pressure	<u>0</u> psig	psig	psig
End of test pressure	<u>0</u> psig	psig	psig
CASING / TUBING	ANNULUS	PRESSURE	
0 minutes	<u>1530</u> psig	psig	psig
5 minutes	<u>1532</u> psig	psig	psig
10 minutes	<u>1533</u> psig	psig	psig
15 minutes	<u>1535</u> psig	psig	psig
20 minutes	<u>1537</u> psig	psig	psig
25 minutes	<u>1538</u> psig	psig	psig
30 minutes	<u>1539</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No


MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

13-28-8-18 Conversion MIT

6/30/2014 2:20:22 PM





Well Name: Federal 13-28-8-18

Job Detail Summary Report

Sundry Number: 52916 API Well Number: 43047327430000

Jobs			
Primary Job Type Conversion	Job Start Date 6/25/2014	Job End Date 6/30/2014	
Daily Operations			
Report Start Date 6/25/2014	Report End Date 6/25/2014	24hr Activity Summary MIRU	
Start Time 16:00	End Time 18:30	Comment Moved From 10-31-8-18: MIRUSU, RDPU, BMW H/O Pmped 60BW d/Csg, LD & Stripped Polished Rod, US Rod Pmp, Flushed Rods w/ 40BW, Soft Seat & Test Tbg, 5BW to Fill, Tbg Failed @ 3200psi, LD 20- 7/8" 4per...SWIFN	
Start Time 18:30	End Time 19:00	Comment c/Travl	
Report Start Date 6/26/2014	Report End Date 6/26/2014	24hr Activity Summary CONT TOOH RDS, RELEASES TAC, NU WTF BOP, RU WORKFLOOR	
Start Time	End Time	Comment	
Report Start Date 6/27/2014	Report End Date 6/27/2014	24hr Activity Summary Cont POOH w/ Tbg	
Start Time 05:30	End Time 06:00	Comment c/Travl	
Start Time 06:00	End Time 18:30	Comment SICP 75psi SITP 75psi, Cont POOH w/ Tbg, LD BHA, 30' of Fill in Tail Jts, MU Slauch Scraper, TIH to 6000', POOH Breaking & Redoping 143- Jts, H/O Flushed Tbg w/ 20BW, LD Remaining 44- Jts on Tri, LD Scraper, MU WTF AS-1X PKR Assa., TIH w/ 143- Jts, H/O Pmped 10BW Pad, Drop SValv, 25BW to Fill Tbg, PT to 3050psi, 20psi Loss Every 15Min For 60Min, Repress to 3050psi, Left Press on Tbg...SWIFWE	
Start Time 18:30	End Time 19:00	Comment C/Travl	
Report Start Date 6/30/2014	Report End Date 6/30/2014	24hr Activity Summary RDMOS, Conduct MIT	
Start Time 05:30	End Time 06:00	Comment c/Travl	
Start Time 06:00	End Time 16:30	Comment SICP 400psi SITP 2550psi, 500psi Loss Over Weekend, BMW H/O Repress to 3050psi, NO PRESSURE LOSS in 45Min GOOD TEST, Retrieve SValv, RD Workfloor, ND BOP, MU I/Tree, XO Ball Valves, H/O Pmped 60BW d/ Annulus w/ Multi-Chem PKR Fluids, Set AS-1X Injection PKR CE @ 4548' w/ 1500# of Tension, NU I/Tree, 15BW to Fill Annulus, PT to 1530psi, NO PRESSURE LOSS in 60Min, MIT Performed By Newfield Wtr Service...RDMOS	
Start Time 16:30	End Time 17:00	Comment Initial MIT on the above listed well. On 06/30/2014 the casing was pressured up to 1539 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 0 psig during the test. There was not an EPA representative available to witness the test.	
Start Time 17:00	End Time 17:30	Comment EPA# UT22197-10513 5:00PM c/Travl	

NEWFIELD

Schematic

Well Name: Federal 13-28-8-18


Surface Legal Location 28-8S-18E		API/UWI 43047327430000	Well RC 500151305	Lease	State/Province Utah	Field Name GMBU CTB9	County UINTAH
Spud Date	Rig Release Date	On Production Date 6/1/1996	Original KB Elevation (ft) 4,965	Ground Elevation (ft) 4,955	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 6,053.0	

Most Recent Job

Job Category Production / Workover	Primary Job Type Conversion	Secondary Job Type Basic	Job Start Date 6/25/2014	Job End Date 6/30/2014
---------------------------------------	--------------------------------	-----------------------------	-----------------------------	---------------------------

TD: 6,250.0

Vertical - Original Hole, 7/1/2014 12:36:49 PM



NEWFIELD**Newfield Wellbore Diagram Data
Federal 13-28-8-18**

Surface Legal Location 28-8S-18E		API/UWI 43047327430000		Lease	
County UINTAH	State/Province Utah		Basin	Field Name GMBU CTB9	
Well Start Date 1/2/2000	Spud Date		Final Rig Release Date	On Production Date 6/1/1996	
Original KB Elevation (ft) 4,965	Ground Elevation (ft) 4,955	Total Depth (ftKB) 6,250.0		Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 6,053.0

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	5/2/1996	8 5/8	8.097	24.00	J-55	319
Production	5/10/1996	5 1/2	4.950	15.50	J-55	6,100

Cement**String: Surface, 319ftKB 5/2/1996**

Cementing Company HALLIBURTON	Top Depth (ftKB) 10.0	Bottom Depth (ftKB) 319.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description CLASS "G" W/2% CaCl2 AND 1/4# /SK FLOCELE	Fluid Type Lead	Amount (sacks) 200	Class TYPE 5	Estimated Top (ftKB) 10.0

String: Production, 6,100ftKB 5/10/1996

Cementing Company HALLIBURTON	Top Depth (ftKB) 1,234.0	Bottom Depth (ftKB) 6,250.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description	Fluid Type 1	Amount (sacks) 160	Class HiFill	Estimated Top (ftKB) 1,234.0
Fluid Description W /2% GEL, 10% SALT, 0.5% HALAD 322	Fluid Type 2	Amount (sacks) 600	Class 50/50 POZ	Estimated Top (ftKB) 3,125.0

Tubing Strings

Tubing Description					Run Date	Set Depth (ftKB)		
Tubing					6/30/2014	4,558.3		
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	143	2 7/8	2.441	6.50	J-55	4,532.27	10.0	4,542.3
Pump Seating Nipple	1	2 7/8				1.10	4,542.3	4,543.4
On-Off Tool	1	2 7/8				1.45	4,543.4	4,544.8
Seal Nipple	1	2 7/8				0.33	4,544.8	4,545.2
Packer	1	5 1/2				6.95	4,545.2	4,552.1
Cross Over	1	2 3/8				0.51	4,552.1	4,552.6
Tubing Pup Joint	1	2 3/8				4.05	4,552.6	4,556.7
XN Nipple	1	2 3/8				1.22	4,556.7	4,557.9
Wireline Guide	1	2 3/8				0.40	4,557.9	4,558.3

Rod Strings

Rod Description				Run Date		Set Depth (ftKB)	
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

Other In Hole

Des	Top (ftKB)	Btm (ftKB)	Run Date	Pull Date
Fill	6,025	6,053	4/2/2009	

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
6	GB6, Original Hole	4,594	4,602	4	90		9/24/2008
5	DS2, Original Hole	4,964	4,972	4	90		9/24/2008
4	D2, Original Hole	5,090	5,100	4	90		9/24/2008
1	A3, Original Hole	5,593	5,610	2	180		5/19/1996
3	A3, Original Hole	5,593	5,610	4	90		9/24/2008
2	CP1/CP2, Original Hole	5,888	5,894	4	90		9/24/2008
2	CP1/CP2, Original Hole	5,924	5,940	4	90		9/24/2008

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	1,546		24.0	3,130			
2	1,472	0.68	16.0	3,721			
3	6,500		14.7	6,500			
4	1,915	0.81	14.6	3,882			
5	1,983	0.83	16.1	4,060			
6	1,908	0.85	16.0	4,740			

NEWFIELD**Newfield Wellbore Diagram Data
Federal 13-28-8-18**

Proppant		
Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		Proppant Bulk Sand 26300 lb
2		Proppant Bulk Sand 45122 lb
3		Proppant Bulk Sand 15025 lb
4		Proppant Bulk Sand 55043 lb
5		Proppant Bulk Sand 35022 lb
6		Proppant Bulk Sand 22569 lb

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-36442
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: FEDERAL 13-28
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2007 FSL 0704 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSW Section: 28 Township: 08.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047327430000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/14/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TUBING	
	<input checked="" type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> <p>The above reference well was put on injection at 11:00 AM on 08/14/2014. EPA # UT22197-10513</p> </div> <div style="width: 35%; text-align: right;"> <p>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 22, 2014</p> </div> </div>		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 8/21/2014	